



SRM VALLIAMMAI ENGINEERING COLLEGE
(An Autonomous Institution)



SRM Nagar, Kattankulathur-603203.

**DEPARTMENT OF ARTIFICIAL INTELLIGENCE
AND DATA SCIENCE**

&

DEPARTMENT OF INFORMATION TECHNOLOGY
ACADEMIC YEAR: 2025-2026

EVEN SEMESTER

LAB MANUAL

(REGULATION - 2023)

**AD3466- DATA COMMUNICATION AND
NETWORKS LAB**

FOURTH SEMESTER

Prepared By

Ms.R.Lakshmi, Assistant Professor / AI&DS

Dr.S.Sekar, Associate Professor / IT

Mr. S.Suresh Kumar, Assistant Professor / IT

OBJECTIVES:

- To understand examine the network protocol and analyser
- To learn to implement TCP sockets
- To visualize the Simulation of DNS
- To build simulating ARP /RARP protocols
- To study Network simulator

LIST OF EXPERIMENTS:

1. Learn to use commands like tcpdump, netstat, ifconfig, nslookup and traceroute. Capture ping and trace route PDUs using a network protocol analyser and examine.
2. Write a HTTP web client program to download a web page using TCP sockets.
3. Applications using TCP sockets like: a) Echo client and echo server b) Chat
4. Simulation of DNS using UDP sockets.
5. Use a tool like Wireshark to capture packets and examine the packets
6. Write a code simulating ARP / RARP protocols.
7. Study of Network simulator (NS) and Simulation of Congestion Control Algorithms using NS.
8. Study of TCP/UDP performance using Simulation tool.
9. Simulation of Distance Vector/ Link State Routing algorithm.
10. Simulation of an error correction code (like CRC).

TOTAL: 45 PERIODS**List of Equipment:** (30 Students per Batch)

Java, HTML5, NS2 simulator (Open source software)

OUTCOMES:**At the end of the course, the student should be able to:**

- Understand and examine the network protocol and analyser.
- Learn and implement TCP sockets.
- Visualize the Simulation of DNS.
- Build simulating ARP /RARP protocols
- Experience the Network simulator.

CO – PO – PSO Mapping

CO	PO												PSO			
	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4
1	3	-	-	3	-	-	-	-	-	-	-	-	3	-	1	-
2	-	2	-	2	2	-	-	-	-	-	-	-	3	-	3	-
3	2	-	3	-	1	-	-	-	3	-	1	-	-	-	3	-
4	-	3	-	3	-	-	-	-	-	-	-	3	-	-	1	-
5	3	-	-	1	2	-	-	-	-	-	-	-	2	-	2	-
Average	2.7	2.5	3.0	2.3	1.7	-	-	-	3.0	-	1.0	3.0	2.7	-	2.0	-

PROGRAMME EDUCATIONAL OBJECTIVES (PEOs)

1.**PEO1:**To afford the necessary background in the field of Artificial Intelligence and data Science to deal with engineering problems to excel as engineering professionals in industries.

2.**PEO2:**To improve the qualities like creativity, leadership, teamwork and skill thus contributing towards the growth and development of society

3.**PEO3:**To develop ability among students towards innovation and entrepreneurship that caters to the needs of Industry and society.

4.**PEO4:**To inculcate and attitude for life-long learning process through the use of Artificial Intelligence and Data Science sources.

5.**PEO5:**To prepare then to be innovative and ethical leaders, both in their chosen profession and in other activities

.PROGRAMME OUTCOMES (POs)

After going through the four years of study, Graduates will exhibit ability to:

1.**Engineering knowledge:** Apply the knowledge of mathematics, science, engineering fundamentals, and an engineering specialization to the solution of complex engineering problems.

2.**Problem analysis:** Identify, formulate, review research literature, and analyze complex engineering problems reaching substantiated conclusions using first principles of mathematics, natural sciences, and engineering

sciences.

3.Design/development of solutions: Design solutions for complex engineering problems and design system components or processes that meet the specified needs with appropriate consideration for the public health and safety, and the cultural, societal, and environmental considerations.

4.Conduct investigations of complex problems: Use research-based knowledge and research methods including design of experiments, analysis and interpretation of data, and synthesis of the information to provide valid conclusions.

5.Modern tool usage: Create, select, and apply appropriate techniques, resources, and modern engineering and IT tools including prediction and modelling to complex engineering activities with an understanding of the limitations.

6.The engineer and society: Apply reasoning informed by the contextual knowledge to assess societal, health, safety, legal and cultural issues and the consequent responsibilities relevant to the professional engineering practice.

7.Environment and sustainability: Understand the impact of the professional engineering solutions in societal and environmental contexts, and demonstrate the knowledge of, and need for sustainable development.

8.Ethics: Apply ethical principles and commit to professional ethics and responsibilities and norms of the engineering practice.

9.Individual and team work: Function effectively as an individual, and as a member or leader in diverse teams, and in multidisciplinary settings.

10.Communication: Communicate effectively on complex engineering activities with the engineering community and with society at large, such as, being able to comprehend and write effective reports and design documentation, make effective presentations, and give and receive clear instructions.

11.Project management and finance: Demonstrate knowledge and understanding of the engineering and management principles and apply these to one's own work, as a member and leader in a team, to manage projects and in multidisciplinary environments.

12.Life-long learning: Recognize the need for, and have the preparation and ability to engage in independent and life-long learning in the broadest context of technological change.

PROGRAM SPECIFIC OUTCOMES (PSOs)

After the completion of Bachelor of Technology in Artificial Intelligence and Data Science programme the student will have following Program specific outcomes

PSO1:Design and develop secured database applications with data analytical approaches of data preprocessing, optimization, visualization techniques and maintenance using state of the art methodologies based on ethical values.

PSO2:Design and develop intelligent systems using computational principles, methods and systems for extracting knowledge from data to solve real time problems using advanced technologies and tools.

PSO3:Design, plan and setting up the network that is helpful for contemporary business environments using latest software and hardware.

PSO4: Planning and defining test activities by preparing test cases that can predict and correct errors ensuring a socially transformed product catering all technological needs.

Course Outcomes:

COURSE NAME: AD3466 – DATA COMMUNICATIONS AND NETWORKS LABORATORY

YEAR OF STUDY: 2024-2025

AD3466.1	Understand and examine the network protocol and analyzer.
AD3466.2	Learn and implement TCP sockets.
AD3466.3	Visualize the Simulation of DNS.
AD3466.4	Build simulating ARP /RARP protocols.
AD3466.5	Experience the Network simulator.

CO-PO-PSO Matrix:

CO	PO1	PO2	PO3	PO4	PO5	PO6	PO7	PO8	PO9	PO10	PO11	PO12
AD3466.1	3	-	-	3	-	-	-	-	-	-	-	-
AD3466.2	-	2	-	2	2	-	-	-	-	-	-	-
AD3466.3	2	-	3	-	1	-	-	-	3	-	1	-
AD3466.4	-	3	-	3	-	-	-	-	-	-	-	3
AD3466.5	3	-	-	1	2	-	-	-	-	-	-	-

CO-PO Justification:

Course Outcome	Program Outcome	Value	Justification
AD3466.1	PO1	3	Understanding network protocols (like TCP/IP, HTTP, DNS) and using network analysers (like Wireshark) requires applying engineering fundamentals such as OSI model, data communication theory and using mathematical/logical skills to troubleshoot and interpret packet data.
	PO4	3	Network analysis often involves Formulating Hypotheses Capturing data via packet sniffers and analysing and interpreting protocol behaviours
AD3466.2	PO2	2	Socket programming helps students analyze real-world networking problems like latency, connection drops, and resource sharing
	PO4	2	Exploring how TCP sockets behave under various conditions - high latency, packet loss, multiple connections and investigating edge cases and performance bottlenecks, capturing data (e.g., using Wireshark) to draw conclusions.
	PO5	2	Applying network emulators or simulators to test robustness of the implementations and understand limitations of tools like blocking vs. non-blocking sockets, thread vs. event-driven models.
AD3466.3	PO1	2	Applying fundamental networking knowledge and computer science principles to simulate and understand DNS resolution, including the layered architecture of DNS query propagation and response
	PO3	3	Designing and implementing a modular simulation of the DNS system that replicates real-world client-server interactions, addressing functional accuracy and system reliability as key design goals.
	PO5	1	Utilizing tools such as DNS simulation platforms, Wireshark, nslookup, and custom scripts to model and analyze DNS behavior, demonstrating proficiency in applying modern IT tools to real-time network resolution scenarios.
	PO9	3	Collaborating in teams to build DNS simulation modules, delegate roles for different DNS server types (e.g., root, TLD), and integrate components to form a functioning distributed name resolution system.
	PO11	1	Developing the DNS simulation project by planning tasks, setting milestones, and managing version control and testing phases, showcasing fundamental project management principles in a technical team environment.
AD3466.4	PO2	3	Analyzing the problem of IP-to-MAC (and MAC-to-IP) resolution in local networks and simulate ARP/RARP behavior using first principles of networking, enabling them to identify and troubleshoot addressing conflicts and packet delivery failures.
	PO4	3	Investigating how ARP and RARP function under different network scenarios through simulation and packet analysis, interpreting protocol behavior and drawing conclusions about network health and vulnerabilities.
	PO12	3	Developing a mindset of continuous learning and adaptation to emerging network technologies and protocols (e.g., IPv6's Neighbor Discovery Protocol).
AD3466.5	PO1	3	Applying foundational networking theories—such as IP addressing, routing algorithms, and protocol stacks—to solve realistic network design and connectivity problems.
	PO4	1	Investigating network behaviors—such as routing loops, congestion, or packet drops—by simulating complex topologies and protocols, enabling systematic data analysis, performance monitoring, and informed problem resolution.

	PO5	2	Utilizing modern network simulation tools like Cisco Packet Tracer or NS3, demonstrate the ability to design, simulate, and analyze networks virtually, while understanding the limitations and assumptions of simulation-based testing
--	-----	---	---

CO-PSO Matrix:

CO	PSO1	PSO2	PSO3	PSO4
AD3466.1	3	-	1	-
AD3466.2	3	-	3	-
AD3466.3	-	-	3	-
AD3466.4	-	-	1	-
AD3466.5	2	-	2	-

CO –PSO Justification:

Course Outcome	PSO	Value	Justification
AD3466.1	PSO1	3	Understanding and examining various network protocols and using network analyzers like Wireshark to inspect and interpret network traffic, to develop a deep technical knowledge of communication systems
	PSO3	1	Gaining the analytical skills required to solve real-world problems in network monitoring and security
AD3466.2	PSO1	3	Implementing TCP socket programming, to gain a strong understanding of core networking concepts and client-server communication
	PSO3	3	Developing practical skills to design, analyze, and debug real-time network applications using modern development tools
AD3466.3	PSO3	3	By visualizing the simulation of DNS operations such as name resolution, caching, and query propagation, to apply analytical thinking and utilize modern tools to better understand and troubleshoot network behavior
AD3466.4	PSO3	1	Building simulations of ARP and RARP protocols, to develop the ability to use modern tools and apply analytical thinking to understand, troubleshoot, and solve complex network addressing problems
AD3466.5	PSO1	2	Experiencing and interacting with a network simulator, to strengthen the foundational knowledge of network architectures and protocols.
	PSO3	2	Developing analytical skills to investigate network performance and Enhancing problem-solving through simulation and analysis.

CO-PO-PSO Mapping(Planned)

CO	PO1	PO2	PO3	PO4	PO5	PO6	PO7	PO8	PO9	PO10	PO11	PO12	PSO1	PSO2	PSO3	PSO4
AD3466	2.7	2.5	3.0	2.3	1.7	-	-	-	3.0	-	1.0	3.0	2.7	-	2.0	-

ASSESSMENT METHOD

MARK SPLIT UP	
AIM & PRE LAB VIVA QUESTIONS	20
OBSERVATION	30
CONDUCTION & EXECUTION	30
OUTPUT & RESULT	10
POST LAB VIVA QUESTIONS	10
TOTAL	100

TABLE OF CONTENTS

E.NO	EXPERIMENT NAME	Pg. No.
1	Networking Commands	10
2	Write a HTTP web client program to download a web page using TCP sockets	12
3a	Socket program For Echo	15
3b	Client- Server application for Chat	18
4	Simulation of DNS using UDP sockets.	21
5	Use a tool like Wireshark to capture packets and examine the packets.	24
6a	Write a code simulating ARP protocols.	26
6b	Write a code simulating RARP protocols.	29
7	Study of Network simulator and Simulation of Congestion Control Algorithms using NS.	32
8	Study of TCP/UDP performance using Simulation tool.	37
9a	Simulation of Distance Vector Routing algorithm.	41
9b	Simulation of Link State Routing algorithm.	44
10	Simulation of error correction code (like CRC).	47
11	*TOPIC BEYOND SYLLABUS: Performance evaluation of Routing protocols using Simulation tool.	52

1.NETWORKING COMMANDS

AIM:

To study the basic networking commands.

NETWORKING COMMANDS:

C:\>arp -a: ARP is short form of address resolution protocol, It will show the IP address of your computer along with the IP address and MAC address of your router.

C:\>hostname: This is the simplest of all TCP/IP commands. It simply displays the name of your computer.

C:\>ipconfig: The ipconfig command displays information about the host (the computer your sitting at)computer TCP/IP configuration.

C:\>ipconfig /all: This command displays detailed configuration information about your TCP/IP connection including Router, Gateway, DNS, DHCP, and type of Ethernet adapter in your system.

C:\>Ipconfig /renew: Using this command will renew all your IP addresses that you are currently (leasing) borrowing from the DHCP server. This command is a quick problem solver if you are having connection issues, but does not work if you have been configured with a static IP address.

C:\>Ipconifg /release: This command allows you to drop the IP lease from the DHCP server.

C:\>ipconfig /flushdns: This command is only needed if you're having trouble with your networks DNS configuration. The best time to use this command is after network configuration frustration sets in, and you really need the computer to reply with flushed.

C:\>nbtstat -a: This command helps solve problems with NetBIOS name resolution. (Nbt stands for NetBIOS over TCP/IP)

C:\>netdiag: Netdiag is a network testing utility that performs a variety of network diagnostic tests, allowing you to pinpoint problems in your network. Netdiag isn't installed by default, but can be installed from the Windows XP CD after saying no to the install. Navigate to the CD ROM drive letter and open the support\tools folder on the XP CD and click the setup.exe icon in the support\tools folder.

C:\>netstat: Netstat displays a variety of statistics about a computers active TCP/IP connections. This tool is most useful when you're having trouble with TCP/IP applications such as HTTP, and FTP.

C:\>nslookup: Nslookup is used for diagnosing DNS problems. If you can access a resource by specifying an IP address but not it's DNS you have a DNS problem.

C:\>pathping: Pathping is unique to Window's, and is basically a combination of the Ping and Tracert commands. Pathping traces the route to the destination address then launches a 25 second test of each router along the way, gathering statistics on the rate of data loss along each hop.

C:\>ping: Ping is the most basic TCP/IP command, and it's the same as placing a phone call to your best friend. You pick up your telephone and dial a number, expecting your best friend to reply with "Hello" on the other end. Computers make phone calls to each other over a network by using a Ping command. The Ping commands main purpose is to place a phone call to another computer on the network, and request an answer. Ping has 2 options it can use to place a phone call to another computer on the network. It can use the computers name or IP address.

C:\>route: The route command displays the computers routing table. A typical computer, with a single network interface, connected to a LAN, with a router is fairly simple and generally doesn't pose any network problems. But if you're having trouble accessing other computers on your network, you can use the route command to make sure the entries in the routing table are correct.

C:\>tracert: The tracert command displays a list of all the routers that a packet has to go through to get from the computer where tracert is run to any other computer on the internet.

Viva Questions and Answers:

1. What is the use of arp -a?

It will show the IP address of your computer along with the IP address and MAC address of your router.

2. What is the use of netstat?

Netstat displays a variety of statistics about a computers active TCP/IP connections. This tool is most useful when you're having trouble with TCP/IP applications such as HTTP, and FTP.

3. What is the use of ipconfig?

The ipconfig command displays information about the host (the computer your sitting at)computer TCP/IP configuration.

4. What is the use of ping?

The Ping commands main purpose is to place a phone call to another computer on the network, and request an answer. Ping has 2 options it can use to place a phone call to another computer on the network. It can use the computers name or IP address.

5. What is the use of tracert?

The tracert command displays a list of all the routers that a packet has to go through to get from the computer where tracert is run to any other computer on the internet.

RESULT:

Thus the above list of primitive has been studied.

2. Write a HTTP web client program to download a web page using TCP sockets

AIM:

To Write a HTTP web client program to download a web page using TCP sockets.

ALGORITHM:

CLIENT SIDE:

- 1) Start the program.
- 2) Create a socket which binds the Ip address of server and the port address to acquire service.
- 3) After establishing connection send the url to server.
- 4) Open a file and store the received data into the file.
- 5) Close the socket.
- 6) End the program.

SERVER SIDE

- 1) Start the program.
- 2) Create a server socket to activate the port address.
- 3) Create a socket for the server socket which accepts the connection.
- 4) After establishing connection receive url from client.
- 5) Download the content of the url received and send the data to client.
- 6) Close the socket.
- 7) End the program.

PROGRAM

```
import javax.swing.*;
import java.net.*;
import java.awt.image.*;
import javax.imageio.*;
import java.io.*;
import java.awt.image.BufferedImage;
import java.io.ByteArrayOutputStream;
import java.io.File;
import java.io.IOException;
import javax.imageio.ImageIO;
public class Client{
public static void main(String args[]) throws Exception
{
Socket soc;
BufferedImage img = null;
soc=new Socket("localhost",4000);
System.out.println("Client is running. ");
try {
System.out.println("Reading image from disk. ");
img = ImageIO.read(new File("digital_image_processing.jpg"));
ByteArrayOutputStream baos = new ByteArrayOutputStream();ImageIO.write(img, "jpg", baos);
```

```

baos.flush();
byte[] bytes = baos.toByteArray();
baos.close();
System.out.println("Sending image to server. ");
OutputStream out = soc.getOutputStream();
DataOutputStream dos = new DataOutputStream(out);
dos.writeInt(bytes.length);
dos.write(bytes, 0, bytes.length);
System.out.println("Image sent to server. ");
dos.close();
out.close();
}
catch (Exception e) { System.out.println("Exception: " + e.getMessage());
soc.close();
}
soc.close();
}
}

```

SERVER PROGRAM

```

import java.net.*;
import java.io.*;
import java.awt.image.*;
import javax.imageio.*;
import javax.swing.*;
class Server {
public static void main(String args[]) throws Exception{
ServerSocket server=null;
Socket socket;
server=new ServerSocket(4000);
System.out.println("Server Waiting for image");
socket=server.accept();
System.out.println("Client connected.");
InputStream in = socket.getInputStream();
DataInputStream dis = new DataInputStream(in);
int len = dis.readInt();
System.out.println("Image Size: " + len/1024 + "KB");
byte[] data = new byte[len];
dis.readFully(data);
dis.close();
in.close();
InputStream ian = new ByteArrayInputStream(data);
BufferedImage bImage = ImageIO.read(ian);
JFrame f = new JFrame("Server");
ImageIcon icon = new ImageIcon(bImage);
JLabel l = new JLabel();
    l.setIcon(icon);
    f.add(l);
    f.pack();
    f.setVisible(true); }}

```

OUTPUT

```
Server waiting for image
Client connected.
Image Size: 29KB
```

Viva Questions and Answers:

1. What is meant by socket?

A socket is a software object that acts as an end point establishing a bidirectional network communication link between a server-side and a client-side program.

2. Define HTTP.

HTTP means HyperText Transfer Protocol. HTTP is the underlying protocol used by the World Wide Web and this protocol defines how messages are formatted and transmitted, and what actions Web servers and browsers should take in response to various commands.

3. What is meant by client server communication?

Client-server model is a distributed application structure that partitions tasks or workloads between the providers of a resource or service, called servers, and service requesters, called clients.

4. Define webpage.

A web page or webpage is a document commonly written in HTML (Hypertext Markup Language) that is accessible through the Internet or other networks using an Internet browser.

5. Define URL.

URL stands for Uniform Resource Locator, and is used to specify addresses on the World Wide Web. A URL is the fundamental network identification for any resource connected to the web (e.g., hypertext pages, images, and sound files). The protocol specifies how information from the link is transferred.

RESULT:

The webpage is successfully downloaded and the contents are displayed and verified.

3. a. SOCKET PROGRAM FOR ECHO

AIM:

To write a socket program for implementation of echo.

ALGORITHM:**CLIENT SIDE**

1. Start the program.
2. Create a socket which binds the Ip address of server and the port address to acquire service.
3. After establishing connection send a data to server.
4. Receive and print the same data from server.
5. Close the socket.
6. End the program.

SERVER SIDE

1. Start the program.
2. Create a server socket to activate the port address.
3. Create a socket for the server socket which accepts the connection.
4. After establishing connection receive the data from client.
5. Print and send the same data to client.
6. Close the socket.
7. End the program.

PROGRAM:**ECHO CLIENT**

```
import java.io.*;
import java.net.*;
public class eclient
{
public static void main(String args[])
{
Socket c=null;
String line;
DataInputStream is,is1;
PrintStream os;
try
{
c=new Socket("localhost",8080);
}
catch(IOException e)
{
System.out.println(e);
}
try
{
```

```

os=new PrintStream(c.getOutputStream());
is=new DataInputStream(System.in);
is1=new DataInputStream(c.getInputStream()); do
{
System.out.println("client");
line=is.readLine();
os.println(line);
if(!line.equals("exit"))
System.out.println("server:"+is1.readLine());
}while(!line.equals("exit"));
}
catch(IOException e)
{
System.out.println("socket closed");
}}

```

Echo Server:

```

import java.io.*; import
java.net.*; import
java.lang.*; public class
eserver
{
public static void main(String args[])throws IOException
{
ServerSocket s=null;
String line;
DataInputStream is;
PrintStream ps; Socket
c=null;
try
{
s=new ServerSocket(8080);
}
catch(IOException e)
{
System.out.println(e);
}
try
{
c=s.accept();
is=new DataInputStream(c.getInputStream());
ps=new PrintStream(c.getOutputStream());
while(true)
{
line=is.readLine();
System.out.println("msg received and sent back to client");
ps.println(line);
}
}
}

```

```
}  
catch(IOException e)  
{  
System.out.println(e);  
}  
}  
}
```

OUTPUT:

CLIENT

Enter the IP address 127.0.0.1

CONNECTION ESTABLISHED

Enter the data CSE

Client received CSE

SERVER

CONNECTION ACCEPTED

Server received CSE

Viva Questions and Answers:

1. what is meant by socket programming?

Socket programs are used to communicate between various processes usually running on different systems. It is mostly used to create a client-server environment.

2. what is the use of java.net?

The java.net package provides 4 kinds of Sockets: Socket is a TCP client API, and will typically be used to connect to a remote host. ServerSocket is a TCP server API, and will typically accept connections from client sockets. Datagram Socket is a UDP endpoint API and is used to send and receive datagram packets.

3. Define echo.

Echo describes when data is sent to a computer or other network devices, and that information is sent back to verify the information was received. Echo can be a command used with operating systems, network devices, or a function of a device.

RESULT:

Thus the program for simulation of echo server was written & executed.

3.b. CLIENT- SERVER APPLICATION FOR CHAT

AIM:

To write a client-server application for chat using TCP

ALGORITHM:

CLIENT

1. Start the program
2. Include necessary package in java
3. To create a socket in client to server.
4. The client establishes a connection to the server.
5. The client accept the connection and to send the data from client to server.
6. The client communicates the server to send the end of the message
7. Stop the program.

SERVER

1. Start the program
2. Include necessary package in java
3. To create a socket in server to client
4. The server establishes a connection to the client.
5. The server accept the connection and to send the data from server to client and
6. vice versa
7. The server communicate the client to send the end of the message.
8. Stop the program.

PROGRAM:

TCPserver1.java

```
import java.net.*;
import java.io.*;

public class TCPserver1
{
    public static void main(String arg[])
    {
        ServerSocket s=null;
        String line;
        DataInputStream is=null,is1=null;
        PrintStream os=null;
        Socket c=null;
        try
        {
            s=new ServerSocket(9999);
        }
        catch(IOException e)
        {
            System.out.println(e);
        }
        try
        {
```

```

c=s.accept();
is=new DataInputStream(c.getInputStream());
is1=new DataInputStream(System.in);
os=new PrintStream(c.getOutputStream());
do
{
line=is.readLine();
System.out.println("Client:"+line);
System.out.println("Server:");
line=is1.readLine(); os.println(line);
}
while(line.equalsIgnoreCase("quit")==false);
is.close();
os.close();
}
catch(IOException e)
{
System.out.println(e);
}
}
}

```

TCPclient1.java

```

import java.net.*;
import java.io.*;

public class TCPclient1
{
public static void main(String arg[])
{
Socket c=null;
String line;
DataInputStream is,is1;
PrintStream os;
try
{
c=new Socket("10.0.200.36",9999);
}
catch(IOException e)
{
System.out.println(e);
}
try
{
os=new PrintStream(c.getOutputStream());
is=new DataInputStream(System.in);
is1=new DataInputStream(c.getInputStream());
do
{
System.out.println("Client:");
line=is.readLine(); os.println(line);

```

```

System.out.println("Server:" + is1.readLine());
}
while(line.equalsIgnoreCase("quit")==false);
is1.close();
os.close();
}
catch(IOException e)
{
System.out.println("Socket Closed!Message Passing is over");
}}

```

OUT PUT :

SERVER

```

C:\Program Files\Java\jdk1.5.0\bin>javac TCPserver1.java Note:
TCPserver1.java uses or overrides a deprecated API. Note:
Recompile with -deprecation for details. C:\Program
Files\Java\jdk1.5.0\bin>java TCPserver1

```

```

Client: Hai Server
Server: Hai Client Client:
How are you Server: Fine
Client: quit
Server: quit

```

CLIENT

```

C:\Program Files\Java\jdk1.5.0\bin>javac TCPclient1.java
Note: TCPclient1.java uses or overrides a deprecated API.
Note: Recompile with -deprecation for details. C:\Program
Files\Java\jdk1.5.0\bin>java TCPclient1

```

```

Client: Hai Server
Server: Hai Client
Client: How are you
Server: Fine Client: quit
Server: quit

```

Viva Questions and Answers:

1. Define chat.

A real-time communication via keyboard between two or more users on a local network (LAN) or over the Internet

2. Define TCP.

TCP/IP stands for Transmission Control Protocol/Internet Protocol, which is a set of networking protocols that allows two or more computers to communicate. The Defense Data Network, part of the Department of Defense, developed TCP/IP, and it has been widely adopted as a networking standard.

3. What is socket API?

A socket API is an application programming interface (API), usually provided by the operating system, that allows application programs to control and use network sockets. Internet socket APIs are usually based on the Berkeley sockets standard.

RESULT:

Thus the above program a client-server application for chat using TCP / IP was executed and successfully.

4. Simulation of DNS using UDP sockets.

AIM:

To write a program to Simulation of DNS using UDP sockets..

ALGORITHM:

- 1.Start the program.
- 2.Get the frame size from the user
- 3.To create the frame based on the user request.
- 4.To send frames to server from the client side.
- 5.If your frames reach the server it will send ACK signal to client otherwise it will send NACK signal to client.
- 6.Stop the program

PROGRAM:

/ UDP DNS Server

Udpdnsserver

```
java import java.io.*; import
java.net.*;
public class udpdnsserver
{
private static int indexOf(String[] array, String str)
{
str = str.trim();
for (int i=0; i < array.length; i++)
{
if (array[i].equals(str)) return i;
}
return -1;
}
public static void main(String arg[])throws IOException
{
String[] hosts = {"yahoo.com", "gmail.com","cricinfo.com", "facebook.com"};
String[] ip = {"68.180.206.184", "209.85.148.19","80.168.92.140", "69.63.189.16"};
System.out.println("Press Ctrl + C to Quit");
while (true){
DatagramSocket serversocket=new DatagramSocket(1362);
byte[] senddata = new byte[1021];
byte[] receivedata = new byte[1021];
DatagramPacket recvpack = new DatagramPacket(receivedata, receivedata.length);
serversocket.receive(recvpack);
String sen = new String(recvpack.getData());
```

```

InetAddress ipaddress = recvpack.getAddress();
int port = recvpack.getPort();
String capsent;
System.out.println("Request for host " + sen); if(indexOf
(hosts, sen) != -1) capsent = ip[indexOf (hosts, sen)]; else
capsent = "Host Not Found";
senddata = capsent.getBytes();

DatagramPacket pack = new DatagramPacket (senddata, senddata.length,ipaddress,port);
serversocket.send(pack);
serversocket.close();
}
}
}
//UDP DNS Client –
Udpdnsclient
.java import java.io.*; import java.net.*;
public class udpdnsclient
{
public static void main(String args[])throws IOException
{
BufferedReader br = new BufferedReader(new InputStreamReader(System.in));
DatagramSocket clientsocket = new DatagramSocket();
InetAddress ipaddress; if (args.length == 0) ipaddress =
InetAddress.getLocalHost(); else
ipaddress = InetAddress.getByNamе(args[0]); byte[] senddata = new
byte[1024];
byte[] receivedata = new byte[1024];
int portaddr = 1362;
System.out.print("Enter the hostname : ");
String sentence = br.readLine();
Senddata = sentence.getBytes();

DatagramPacket pack = new DatagramPacket(senddata,senddata.length, ipaddress,portaddr);
clientsocket.send(pack);

DatagramPacket recvpack =new DatagramPacket(receivedata,receivedata.length);
clientsocket.receive(recvpack);

String modified = new String(recvpack.getData());
System.out.println("IP Address: " + modified);
clientsocket.close();
}
}

```

OUTPUT :

Server

```
javac udpdnsserver.java
java udpdnsserver
Press Ctrl + C to Quit Request for host yahoo.com
Request for host cricinfo.com
Request for host youtube.com
```

Client

```
javac udpdnsclient.java
java udpdnsclient
Enter the hostname : yahoo.com IP
Address: 68.180.206.184
java udpdnsclient
Enter the hostname : cricinfo.com IP
Address: 80.168.92.140
java udpdnsclient
Enter the hostname : youtube.com IP
Address: Host Not Found
```

Viva Questions and Answers:

1. Define DNS.

DNS. (Domain Name System) The Internet's system for converting alphabetic names into numeric IP addresses. For example, when a Web address (URL) is typed into a browser, DNS servers return the IP address of the Web server associated with that name.

2. Define UDP.

User Datagram Protocol (UDP) is part of the Internet Protocol suite used by programs running on different computers on a network. UDP is used to send short messages called datagrams but overall, it is an unreliable, connectionless protocol.

3. what is meant by MAC address?

A MAC address is a hardware identification number that uniquely identifies each device on a network.

4. What is meant by IP address?

An Internet Protocol address (IP address) is a numerical label assigned to each device connected to a computer network that uses the Internet Protocol for communication. An IP address serves two principal functions: host or network interface identification and location addressing.

5. List the IP address class.

Class	1 st Octet Decimal Range	Default Subnet Mask
A	1 – 126*	255.0.0.0
B	128 – 191	255.255.0.0
C	192 – 223	255.255.255.0
D	224 – 239	Reserved for Multicasting

RESULT:

Thus the above program a client-server application for chat using UDP was executed and successfully

5 .Use a tool like Wireshark to capture packets and examine the packets.

Aim:

To use a Java program to capture network packets and analyze them. The aim is to understand the structure of packets, extract metadata (e.g., source/destination IP, port, and protocol), and optionally save the data for further analysis.

Algorithm:

- 1. Setup Environment:**
 - Install the jNetPcap library (a Java wrapper for the libpcap library).
 - Ensure necessary dependencies are added to the project.
- 2. Initialize Packet Capture:**
 - Enumerate available network interfaces.
 - Select the interface to monitor.
- 3. Start Capturing Packets:**
 - Open the selected interface for capturing.
 - Define a packet handler to process packets as they arrive.
- 4. Process Packets:**
 - Extract key fields from the packet (e.g., headers, payload).
 - Display or save packet details.
- 5. Stop Capture:**
 - Terminate the packet capture session.
- 6. Output Results:**
 - Show real-time packet details.
 - Optionally, save the captured data to a file.

Java Code:

```
import org.jnetpcap.Pcap;
import org.jnetpcap.PcapIf;
import org.jnetpcap.packet.PcapPacket;
import org.jnetpcap.packet.PcapPacketHandler;

import java.util.ArrayList;
import java.util.List;

public class PacketCapture {

    public static void main(String[] args) {
        List<PcapIf> devices = new ArrayList<>();
        StringBuilder errbuf = new StringBuilder();

        // Get a list of network devices
        int r = Pcap.findAllDevs(devices, errbuf);
        if (r == Pcap.NOT_OK || devices.isEmpty()) {
            System.err.printf("Can't read list of devices, error: %s\n", errbuf.toString());
            return;
        }

        System.out.println("Available network devices:");
        for (int i = 0; i < devices.size(); i++) {
```

```

        System.out.printf("#%d: %s [%s]\n", i, devices.get(i).getName(), devices.get(i).getDescription());
    }

    // Choose the first device
    PcapIf device = devices.get(0);
    System.out.printf("\nChoosing device: %s\n", device.getName());

    // Open the device for packet capturing
    int snaplen = 64 * 1024; // Capture all packets, no truncation

    int flags = Pcap.MODE_PROMISCUOUS; // Capture all traffic
    int timeout = 10 * 1000; // 10 seconds in milliseconds

    Pcap pcap = Pcap.openLive(device.getName(), snaplen, flags, timeout, errbuf);

    if (pcap == null) {
        System.err.printf("Error while opening device for capture: %s\n", errbuf.toString());
        return;
    }

    // Create a packet handler
    PcapPacketHandler<String> packetHandler = (packet, user) -> {
        System.out.printf("Packet captured at %s\n", new java.util.Date(packet.getCaptureHeader().timestampInMillis()));
        System.out.printf("Packet length: %d bytes\n", packet.getCaptureHeader().caplen());
        System.out.println(packet.toString());
    };

    System.out.println("Starting packet capture...");
    pcap.loop(10, packetHandler, "Packet Capture");
    pcap.close();

    System.out.println("Packet capture completed.");
}
}

```

Output:

```

Available network devices:
#0: eth0 [Intel(R) Ethernet Connection]
#1: wlan0 [Wireless Network Adapter]

```

```

Choosing device: eth0
Starting packet capture...
Packet captured at Wed Dec 26 2024 15:35:15 GMT+0000
Packet length: 74 bytes
Packet captured at Wed Dec 26 2024 15:35:16 GMT+0000
Packet length: 60 bytes
...
Packet capture completed.

```

Results:

Thus the program captures and processes packets in real-time has been executed.

6.a. Write a code simulating ARP protocols.

AIM

To implement Address Resolution Protocol .

ALGORITHM

CLIENT SIDE

1. Establish a connection between the Client and Server. `Socket ss=new Socket(InetAddress.getLocalHost(),1100);`
2. Create instance output stream writer `PrintWriter ps=new PrintWriter(s.getOutputStream(),true);`
3. Get the IP Address to resolve its physical address.
4. Send the IPAddress to its output Stream.`ps.println(ip);`
5. Print the Physical Address received from the server.

SERVER SIDE

1. Accept the connection request by the client. `ServerSocket ss=new ServerSocket(2000);Socket s=ss.accept();`
2. Get the IPaddress from its inputstream. `BufferedReader br1=new BufferedReader(newInputStreamReader(s.getInputStream())); ip=br1.readLine();`
3. During runtime execute the processRuntime `r=Runtime.getRuntime(); Process p=r.exec("arp -a "+ip);`
4. Send the Physical Address to the client.

PROGRAM

ARP CLIENT

```
import java.io.*;
import java.net.*;

class ArpClient
{
public static void main(String args[])throws IOException
{
try
{
Socket ss=new Socket(InetAddress.getLocalHost(),1100);
PrintStream ps=new PrintStream(ss.getOutputStream());
BufferedReader br=new BufferedReader(newInputStreamReader(System.in));
String ip;
System.out.println("Enter the IPADDRESS:");
```

```

ip=br.readLine();
ps.println(ip);
String str,data;
BufferedReader br2=new
BufferedReader(newInputStreamReader(ss.getInputStream()));
System.out.println("ARP From Server::");
do
{
str=br2.readLine();
System.out.println(str);
}
while(!(str.equalsIgnoreCase("end")));
}
catch(IOException e)
{
System.out.println("Error"+e);

}}}

```

ARP SERVER

```

import java.io.*;
import java.net.*;

class ArpServer
{
public static void main(String args[])throws IOException
{
try
{
ServerSocket ss=new ServerSocket(1100);
Socket s=ss.accept();
PrintStream ps=new PrintStream(s.getOutputStream());
BufferedReader br1=new BufferedReader(newInputStreamReader(s.getInputStream())); String
ip;
ip=br1.readLine();
Runtime r=Runtime.getRuntime();
Process p=r.exec("arp -a "+ip);
BufferedReader br2=new BufferedReader(newInputStreamReader(p.getInputStream())); String
str;
while((str=br2.readLine())!=null)
{
ps.println(str);
}}
catch(IOException e)
{
System.out.println("Error"+e); }}}

```

OUTPUT

```
C:\Networking Programs>java ArpServer
C:\Networking Programs>java ArpClient
Enter the IPADDRESS:
192.168.11.58
ARP From Server::
Interface: 192.168.11.57 on Interface 0x1000003
Internet Address Physical Address Type
192.168.11.58 00-14-85-67-11-84 dynamic
```

Viva Questions and Answers:

1. Define ARP.

The address resolution protocol (**arp**) is a protocol used by the Internet Protocol (IP) [RFC826], specifically IPv4, to map IP network addresses to the hardware addresses used by a data link protocol.

2. Define IPv4.

IPv4 (**Internet Protocol Version 4**) is the fourth revision of the Internet Protocol (IP) used to identify devices on a network through an addressing system.

RESULT

Thus the implementation of ARP is done & executed successfully.

6.b. Write a code simulating RARP protocols.

AIM:

To write a java program for simulating RARP protocols.

ALGORITHM:

CLIENT

1. Start the program
2. using datagram sockets UDP function is established.
2. Get the MAC address to be converted into IP address.
3. Send this MAC address to server.
4. Server returns the IP address to client.

SERVER

1. Start the program.
2. Server maintains the table in which IP and corresponding MAC addresses are stored.
3. Read the MAC address which is send by the client.
4. Map the IP address with its MAC address and return the IP address to client.

CLIENT:

```
import java.io.*; import
java.net.*;

import java.util.*; class
Clientarp12
{
    public static void main(String args[])
    {
        try
        {
            DatagramSocket client=new DatagramSocket();

            InetAddress addr=InetAddress.getByName("127.0.0.1");

            byte[] sendbyte=new byte[1024];
            byte[] receivebyte=new byte[1024];

            BufferedReader in=new BufferedReader(new InputStreamReader(System.in));
            System.out.println("Enter the Physical address (MAC):");
            String str=in.readLine();
            sendbyte=str.getBytes();
            DatagramPacket sender=new DatagramPacket(sendbyte,sendbyte.length,addr,1309);

            client.send(sender);
            DatagramPacket receiver=new DatagramPacket(receivebyte,receivebyte.length);
            client.receive(receiver);

            String s=new String(receiver.getData());
```

```

        System.out.println("The Logical Address is(IP): "+s.trim());
        client.close();
    }
    catch(Exception e)
    {System.out.println(e);
    }
}
}

```

SERVER:

```

import java.io.*; import
java.net.*; import java.util.*;
class Serverrarp12
{
    public static void main(String args[])
    {
        try
        {
            DatagramSocket server=new DatagramSocket(1309);
            while(true)
            {
                byte[] sendbyte=new byte[1024];
                byte[] receivebyte=new byte[1024];
                DatagramPacket receiver=new DatagramPacket(receivebyte,receivebyte.length);
                server.receive(receiver);
                String str=new String(receiver.getData());
                String s=str.trim();
                InetAddress addr=receiver.getAddress();
                int port=receiver.getPort();
                String ip[]={"165.165.80.80","165.165.79.1"};
                String ac[]={"6A:08:AA:C2","8A:BC:E3:FA"};
                for(int i=0;i<ip.length;i++)
                {
                    if(s.equals(mac[i]))
                    {
                        sendbyte=ip[i].getBytes();
                        DatagramPacket sender=newDatagramPacket(sendbyte,sendbyte.length,addr,port);
                        server.send(sender);
                        break;
                    }
                }
            }
        }
        break;
    }
}

```

```
        }  
    }  
    catch(Exception e)  
    {  
        System.out.println(e);}  
    }  
}
```

OUTPUT:

I:\ex>java Serverrarp12

I:\ex>java Clientrarp12

Enter the Physical address (MAC):

6A:08:AA:C2

The Logical Address is(IP): 165.165.80.80

Viva Questions and Answers:

1. Define RARP.

RARP (Reverse Address Resolution Protocol) is a protocol by which a physical machine in a local area network can request to learn its IP address from a gateway server's Address Resolution Protocol (ARP) table .

2. What is the use of RARP?

RARP is used for the opposite purpose; namely, to convert an ethernet address to an IP address. Its linux-network-administration purpose is to enable diskless machines, such as X workstations, to find out their IP address at boot time.

RESULT:

Thus the implementation of RARP is done & executed successfully.

7. Study of Network simulator (NS) and Simulation of Congestion Control Algorithms using NS.

AIM:

To study of network simulator (ns) and simulation of congestion control algorithms using ns.

SYSTEM REQUIREMENTS:

PC: Pentium or higher

One LAN card onboard or on PCI slot with 10/100Mbps speed. 128MB RAM

500MB free space on Hard drive
CD ROM drive

Serial port, LPT port & USB port installed on system Operating System:
Windows 2000 or higher

THEORY:

LTS-01 Local area network / wireless local area network trainer system:

It is designed to help students understand the basic concepts, modes of operation and protocols involved in networking. The trainer has integrated hardware flow control on panel board for better understanding of different types of LAN topologies involved in networking. The trainer system is provided with windows-based user friendly software with analysis of protocols, different layers, network and measurement of error rate and throughput.

Students can easily do connections in different topologies and can learn actual data transfer either through hardware or through simulated network concept. Facility is provided into system software to introduce errors into packets being sent and analyze the effect of error on different protocols and hence find the effect on throughput graph as well.

Trainer and its various types of experimentation using this system. This system works into server-client base. For any topology user has to select one server and select the network type whether it is LAN or WLAN. To understand the topology concept user can connect two or more clients to hardware. Depending on the topology selected user will have option to select protocols for the selected topology. Upon selection of protocol user can then create network of connected computers.


In any network which is created by user server can send or can communicate with any of the clients however clients can communicate only with server, no client to client communication is possible. Transmitter port protocol & network analysis can be done after communication is over between server and clients. Throughput v/s Packet size graph can be plotted for which at least two file transfers should be carried out. This plot can be printed to attach in the lab exercise sheet.

For the LAN network LAN cards must be installed prior to start work on this trainer. For wire less LAN USB ports should be available on the computers which are to be used for experimentation. In WLAN wireless access cards gets connected to computer USB ports and access point gets connected to hardware device.

L-SIM LAN Protocol Simulator & Analyzer Software:

It is designed to teach the basic concepts, topologies & various protocols involved in networking. The software is provided with analysis of protocols, different layers, network and measurement of error rate and throughput. Facility is provided to introduce errors into packets being sent and analyze the effect of error on different protocols and hence find the effect on throughput graph as well. Software is supported with neat operating instruction manual and online help.


MODEL WINDOW DIAGRAM FOR L-SIM



N-S IM Network simulation software:

It is developed to provide basic understanding and implementation of various advanced concepts in networking. The software provides an opportunity to understand network fundamentals through animations & simulations. The simulation provides for network experimentation with various LAN and WAN protocols, network devices, routers, encryption, decryption, file transfer, error insertion and analysis of error rate and throughput etc. This software covers Ethernet LAN, wireless LAN and router. All networking theory is explained using simulation and animation.

MODEL WINDOW DIAGRAM FOR N-SIM



Rapid advances in computer & communication technologies have resulted in the increasing merger of these two fields. The lines have blurred among computing, switching & digital transmission equipment; and the same digital techniques are being used for data, audio & video transmission. Merging & evolving technologies, coupled with increasing demands for efficient & timely collection, processing & dissemination of information, have led to the development of integrated systems that transmit & process all types of data.

These integrated systems are broadly divided as follows

- **DATA COMMUNICATION** dealing with transmission, transmission media, signal decoding, interfacing, data link control & multiplexing
- **NETWORKING** deals with the technology & architecture of communication network
- **COMMUNICATION PROTOCOLS** which covers the architecture as well as analysis of individual protocols at various layers depending on the hardware & software Network laboratory is designed & developed considering the curriculum offered by Anna University. Trainers offered under network laboratory are designed for students at all level to study and understand all the concepts of data communication, data transfer using serial and parallel ports, Ethernet and wireless LAN with complete protocol understanding and actual hands on with hardware & software with ease.

Network laboratory consists of DCT-03 Data communication trainer kit, LTS- 01 LAN / Wireless LAN training system, L-SIM LAN / WLAN protocol simulator and analyzer software & N-SIM Network simulation software.

The DCT-03: Data communication trainer is a unique trainer kit for the development of exercises and theoretical-experimental courses to understand the basic concept and working of modes and protocols in serial and parallel communication.

The trainer kit consists of functional blocks for serial and parallel communication system.

The trainer kit is highly innovative from a technological as well as an educational point of view. The trainer kit is used as “basic unit” to examine all the peculiar operating standards of serial and parallel communication system. The only external equipments required are two Computers serial and parallel

communication ports and an Oscilloscope. Utmost care has been laid in the design and quality control of all circuits, to ensure the repeatability of the results of the experiments.

Data communication is a term referred when the sender and receiver are digital devices, which communicate with each other by means of binary information. The objective of this trainer kit is to clear the various aspects of the data communications which comprise of

- The information source or sender.
- The medium for carrying information.
- The information receiver.
- The communication protocols, which ensure proper transfer of data.

With an increasing demand in information exchange the field of data communication technique is emerging as the only solution, to satisfy the various needs of today's communication sector and to achieve very high bandwidth along with highest accuracy. The communication media is shifting from analog signal transfer towards digital communication.

With PC becoming the biggest storage devices in digital form, it becomes the main source and destination for information exchange. With rapid growth in both the communication technologies as well as computer hardware and software technologies, these two fields are merged to form a data communication network. Now the digital data is used for data, voice and image transmission.

Depending upon the application the communication link can be of point to point communication between two devices or a multipoint communication between at least 3 devices and data transfer can be serial or in parallel form.

Viva Questions and Answers:

1. Define NS.

A Network Simulator is an object oriented, event driven discrete simulator written in C++, with an object oriented tool command language (OTCL) interpreter as a front end.

2. What protocols does NS support?

A lot! Almost all variants of TCP, several forms of multicast, wired networking, several ad hoc routing protocols and propagation models (but not cellular phones), data diffusion, satellite, and other stuff. See the documentation (described above) for details, or download ns and look.

3. Define data communication.

Data communication is a term referred when the sender and receiver are digital devices, which communicate with each other by means of binary information.

4. List of Network Simulators:

Ns2 (Network Simulator 2).

Ns3 (Network Simulator 3).

OPNET.

OMNeT++.

NetSim.

QualNet.

J-Sim.

5. Define OPNET.

OPNET Network Simulator. OPNET Network simulator is a tool to simulate the behavior and performance of any type of network. The main difference Opnet Network Simulator comparing to other simulators lies in its power and versatility. IT Guru provides pre-built models of protocols and devices.

RESULT:

The study of network simulator (ns) and simulation of congestion control algorithms using ns is executed and verified.

8. Study of TCP/UDP performance using Simulation tool.

AIM:

To Study of TCP/UDP performance using Simulation tool.

TOOLS USED:

Opnet Simulator

INTRODUCTION:

The transport layer protocols provide connection- oriented sessions and reliable data delivery services. This paper seeks to reflect a comparative analysis between the two transport layer protocols, which are TCP/IP and UDP/IP, as well to observe the effect of using these two protocols in a client server network. The similarities and differences between TCP and UDP over the Internet are also presented in our work. We implement a network structure using Opnet Modeler and finally, based on the practical results obtained we present the conclusions-showing the difference between these two protocols and how they work.

The transport layer is not just another layer. It is the heart of the whole protocol hierarchy. Its task is to provide reliable, cost-effective data transport from the source machine to the destination machine, independently of the physical network or networks currently in use.

TCP and UDP are transport layer components that provide the connection point through which applications access network services. TCP and UDP use IP, which is a lower-layer best effort delivery service. IP encapsulates TCP packets and UDP datagrams and delivers this information across router-connected internet works.

The ultimate goal of the transport layer is to provide efficient, reliable, and cost-effective service to its users, normally processes in the application layer. To achieve this goal, the transport layer makes use of the services provided by the network layer. Without the transport layer, the whole concept of layered protocols would make little sense e.g. The Transport Layer prepares applications data for transport over the network and processes network data to be used by applications. It is responsible for the end-to-end transfer of data over the network and is the four of the OSI model. The Transport layer meets a number of functions:

- enabling the applications to communicate over the network at the same time when using a single device;
- ensure that all amount of data is receive by the correct application;
- responsible for fragmentation and reassembly;
- develop mechanism for handling errors.

Comparison Between TCP And UDP

Service	TCP	UDP
Flow controls	The receiver can signal the sender to slow down.	ACKs, which are used in TCP to control packet flow, are not returned.
Connection setup	It takes time, but with TCP reliability is ensured.	No connection is required.

Guaranteed message delivery	Returns acknowledgments.	UDP does not return ACKs, the receiver can't signal that packets have been successfully delivered.
Congestion controls	Network devices can take advantage of TCP ACK to control the behavior of sender.	If ACK, are missing, the network cannot signal congestion to the sender.

A big difference between TCP and UDP is the congestion control algorithm. For the TCP, congestion algorithm prevents the sender from overrunning the network capacity, while TCP can adapt the sender's rate with the network capacity and attempt to avoid potential congestions problems.


User Datagram Protocol (UDP), another transport protocol in IP networks, is described e.g. The User Datagram Protocol (UDP) provides an unreliable connectionless delivery service using IP to transport messages between machines e.g. [5]. It uses IP to carry messages, but adds the ability to distinguish among multiple destinations within a given host computer. Is a connectionless protocol which doesn't provide flow control, reliability or error recovery and the retransmissions of data in case of errors must be ordered by other protocols. UDP is designed for applications that do not have to recombine the data segment that arrives from the sender. In another way, application-level protocols are directly responsible for the security of data transmitted.

Difference from the TCP is that there is no mechanism for error detections. If applications that use UDP doesn't have their own mechanism for information retrieval can lose those data and be forced to retransmitted again. On the other side this applications are not slow down by the confirmation process and the memory will be available for work much faster.

SIMULATION RESULTS:


The simulation time is set for two hours data transfer between LAN network and the server with no packet latency and packet discard ratio of 0% while packets traverse thru the WAN. The task response time, in seconds, Fig. 1, shows how long the application need to be completed. The time when using TCP to complete the task is greater that the one using UDP. When using TCP, source and destination need to perform a three-way handshake before starting sending data and all amount of data need to be acknowledge by the destination when it is receive, so is taking more time than UDP, which doesn't perform this tasks.

Custom Application.Task Response Time




1. Response time for TCP and UDP


PPPServer



2. Traffic received (packets/sec) for the server



3. Traffic/Link utilization from the WAN to the server



4. Link utilization with a 0.5% packets discard ratio

The main difference between these two protocols is that TCP provides reliability and congestion control services, while UDP is orientated to improve performance.

The most important and common thing that TCP and UDP are using is the ability to set a host-to-host communication channel, so the packets will be delivered between processes running on two different computers. UDP is the right choice for application where reliability is not a must but the speed and performance is. Instead, TCP, even if it takes more time for the processes, has additional functions like same order delivery, reliability and flow control. As future work, we plan to conduct several studies regarding packets routing in computer networks to improve the fairness of data transmissions using different network protocols.

RESULT:

Thus the TCP/UDP performance has been simulated successfully using OPNET.

9.a Simulation of Distance Vector Routing algorithm.

AIM:

To implement the Distance – Vector Routing Algorithm

Requirement:

1. VI-RTSIM software.
2. Personal computer.

THEORY:

Distance Vector Algorithm:

- ❖ A Distance vector routing, each router periodically share its knowledge about the entire network with it's neighbors.
- ❖ The three keys to under this algorithm are
 1. Knowledge about the whole network.
 2. Routing only to neighbor.
 3. Information sharing at regular intervals.

Knowledge about the whole work:

- ❖ Each router shares its knowledge about entire network. It sends all of its collected knowledge about the network to its neighbors.

Routing only to neighbor:

- ❖ Each router periodically sends its knowledge about the network only to those routers to which it has direct links. It sends whatever knowledge it has.

Information sharing at regular intervals:

- ❖ The every 30 seconds, each router sends its information about the whole network to its neighbors.

Sharing Information:

- ❖ LAN's are connected by router, represented by the assuming A, B, C, D, E and F.
- ❖ Distance vector routing simplifies the routing process by assuming a lost of one unit for every link.
 - ❖ The efficiency of transmission is a function only of the number of links required to reach a destination. In this, the cost on hop count.

Routing Table:

- ❖ Each router gets its initial knowledge about the internet work and how it uses shared information to update that knowledge.
- ❖ The routing table has e columns network lost router ID.
- ❖ The first block is final destination of packet.
- ❖ The second block is no of hop count.
- ❖ The third block is that to which a packet delivers must.


Updating algorithm:

- ❖ Updating algorithm requires that the router first has one hop to the hop count field for each advertised router.
- ❖ The router should apply the below rules to each router, if the advertised destination is not in routing table

- ❖ If next hop field is same, router should replace the entry in the table with advertised one.
- ❖ If next hop field is same, router should replace the entry in the table with advertised one.
- ❖ . If next hop field is not the same, advertised hop count is smaller than the one in the table, the router should replace the entry in the table with new one.
- ❖ IF advertised hop count is not smaller, the router should do no routing.

PROCEDURE

1. Open VI-RTSIM software from desktop
2. Click the Simulation menu bar
3. Select the “Distance – Vector Routing Algorithm” option from Routing algorithm menu bar.
4. Network with routers connected through link is drawn by using option in editor(add router, join link, delete router, delete link, Add caption to link, add caption to router)
5. Select any two nodes to find the shortest distance between them.
6. Click the Find path Button to run the program.
7. Now the shortest paths between the two nodes are calculated.



Find Shortest Path

Distance vector table:

To	1	2	3	4	5	6	7	8
1	0	300	1000	0	0	0	0	1700
2	300	0	800	0	0	0	0	0
3	1000	800	0	1200	0	0	0	0
4	0	0	1200	0	1500	1000	0	0
5	0	0	0	1500	0	250	0	0
6	0	0	0	1000	250	0	900	1400
7	0	0	0	0	0	0	0	1000

Calculate

Distance: From: 2 To:

Node	1	2	3	4	5	6	7	8
Distance	300	0	800	2000	3250	3000	3000	2000

Path:

Node	1	2	3	4	5	6	7	8
Path	2	0	2	3	6	4	8	1

The path is: 5 <- 6 <- 4 <- 3 <- 2
The distance is: 3250

Viva questions and answers:

1. what is distance vector routing protocol?

In distance vector routing the least cost route between any two nodes is the route with minimum distance. In this each node maintains a vector table of minimum distances to every node. The table at each node also guides the packets to the desired node by showing the next stop in the route.

2. What is advantage in distance vector routing protocol?

In this each node shares its routing table with its immediate neighbors periodically and when there is a change.

3.What are the routing protocols?

- Intra domain routing protocols
- Interdomain routing protocols

3. What is intradomain routing protocols?

Routing inside an autonomous system is referred to as intradomain routing protocols.

4. What is RIP?

RIP(routing information protocol) is an intradomain routing protocol used inside an autonomous system. it is very simple protocol based on distance vector routing.

RESULT:

Thus Distance Vector routing algorithm has been implemented and shortest-path has been circulated.

9.b Simulation of Link State Routing Algorithm.

AIM:

To implement the Link State Routing Algorithm

REQUIREMENT:

1. VI-RTSIM software.
2. Personal computer.

THEORY:

Link State Vector Algorithm:

- ❖ In Link state routing, each router share its information of its neighbors with every other router in the inter-network.

Knowledge about the neighborhood:

- ❖ Instead of sending its entire routing table, a router sends information about its neighborhood only.

To all router:

- ❖ Each router send this information to every other router on the internetworking, not just to its neighbors.
- ❖ If s does so by a process called “flooding” it means that a router sends its information.

Information sharing when there is a Change:

- ❖ Each router sends out information about the neighbors when there is a change.

Information sharing:

- ❖ Link state routing process use the same internet work as distance vector algorithm.
- ❖ Here each other sends its knowledge about is neighbors to every other router in the internet work.
- ❖ Cost is applied only by routers and not by any other station on a network, if cost was added by every station, instead of by routers alone, it would accumulate unpredictably.
- ❖ Cost is applied as a packet leaves the router rather then as if enters. Most networks are broadcast networks. When a packet is in network every station, including the router, can pick it up, we cannot assign any cost to a packet.

Link state packet:

When a router floods the network with information about its neighborhood, it is said to be advertising. The basis of this advertising is a short packet called a link state packet (LSP).

Advertiser	Network	Cost	Neighbor
------------	---------	------	----------

Getting information about neighbors:

- ❖ A router gets its information about its neighbors by periodically sending them a short greeting packet.
- ❖ If the neighbor responds to the greeting as expected, it is assumed to be alive and functioning.

Initialization:

- ❖ Imagine that all routers in our sample internet work come up at the same time.


- ❖ Each router sends a greeting packet to its neighbors to find out the state of each link.

Link – State Database:

- ❖ Every router every LSP and puts the information into a link-state database.
- ❖ Because every router receives the same LSPs every router builds the same database.
- ❖ It stores this database on its disk and uses it to calculate its routing table. If a router is added to be deleted from the system, the whole database must be shared for fast updating.

PROCEDURE

1. Open VI-RTSIM software from desktop
2. Click the Simulation menu bar
3. Select the “Link State Routing Algorithm” option from Routing algorithm menu bar.
4. Network with routers connected through link is drawn by using option in editor(add router, join link, delete router, delete link, Add caption to link, add caption to router)
5. Select any two nodes to find the shortest distance between them.
6. Click the Find path Button to run the program.
7. Now the shortest paths between the two nodes using link state routing algorithm was calculated.



Find Shortest Path

Link State table:

To	A	B	C	D	E	F	G
A	0	1	0	1	1	0	0
B	1	0	1	0	1	0	0
C	0	1	0	0	1	1	0
D	1	0	0	0	1	0	1
E	1	1	1	1	0	1	0
F	0	0	1	0	1	0	0
G	0	0	0	1	0	0	0

Distance: From: A To:

Node	A	B	C	D	E	F	G
Distance	0	1	2	1	1	2	2

Path:

Node	A	B	C	D	E	F	G
Path	0	1	2	1	1	5	4

The path is: F <- E <- A
The distance is: 2

Viva questions and answers:

1. What is link state routing protocol?

It has a different concept from that of distance vector routing. In this each node in the domain has the entire topology of the domain-the list of nodes and links, how they are connected including the type, cost and condition of the links.

2. What is other name of link state routing protocol?

Dijkstra's algorithm.

3. How the routing table is builded?

By formation of a shortest path tree for each node. Calculation of a routing table based on the shortest path tree. Creation of the states of the links by each node.

4. What is periodic update?

A node sends its routing table, normally every 30's in a periodic update. The period depends on the protocol that is using distance vector routing.

RESULT:

Thus Link-State routing algorithm has been implemented and shortest-path has been circulated.

10. Simulation of error correction code (like CRC)

AIM:

To implement and check the error detection/error correction techniques in networks using a c program.

REQUIREMENT:

- 1.Pc-ino
- 2.C/C++ compiler

THEORY:

Error Detection

- Bit errors occur in frames due to electrical interference or thermal noise.
- Detecting errors is one part of the problem; correcting errors is the other.
- What happens when an error is detected?
- Two basic approaches:
 - Notify the sender that message is corrupt so the sender can retransmit it; (most often used in every day applications)
 - Use an error-correcting code to reconstruct the correct message

Transmission Errors

- External electromagnetic signals can cause incorrect delivery of data
 - · Data can be received incorrectly
 - · Data can be lost
 - · Unwanted data can be generated
- Any of these problems are called *transmission errors*

Error Detection


- Detecting Transmission Errors: basic idea is to add redundant information to a frame that can determine if errors have been introduced.

Error Correction or Error Detection?

- When error is detected, frame is discarded and resent, using bandwidth and causing latency, waiting for its arrival.
- Error correction requires additional bit to be sent with every frame.
- Correction is useful when
 - 1) errors are probable or
 - 2) the cost of retransmission is too high

Cyclic Redundancy Check (CRC)

CRC is a different approach to detect if the received frame contains valid data. This technique involves binary division of the data bits being sent. The divisor is generated using polynomials. The sender performs a division operation on the bits being sent and calculates the remainder. Before sending the actual bits, the sender adds the remainder at the end of the actual bits. Actual data bits plus the remainder is called a codeword. The sender transmits data bits as code words.



At the other end, the receiver performs division operation on codewords using the same CRC divisor. If the remainder contains all zeros the data bits are accepted, otherwise it is considered as there some data corruption occurred in transit.

PROCEDURE:

- Start the process.
- Give the data which is the message.
- Compile and run the program.
- Enter the received hamming code.
- The error is corrected codeword.

PROGRAM FOR CODE GENERATION FOR ERROR DETECTION AND CORRECTION

```
#include<stdio.h>
#include<math.h>
#include<stdlib.h>
int main()
{
int i,j,k,count,err-pos=0,flag=0;
char dw[20],cw[20],data[20];
printf("enter data as binary bit stream(7 bits):\n");
scanf("%s",data);
for(i=1,j=0,k=0;i<12;i++)
{
if(i==(int)pow(2,j))
{
dw[i]='?';
j++;
}
else
{

```

```

dw[i]=data[k];
k++;
}
}
for(i=0;j<4;i++)
{
count=0;
for(j=(int)pow(2,i);j<12;j+=1;j+=(int)pow(2,i))
{
for (k=0;k<(int)pow(2,i);k++)
{
if(dw[j]=='1')count++;j++;
}
}
if(count%2==0)
dw[(int)pow(2,i)]=0';
else
dw[(int)pow(2,i)]=1';
}
printf("in code word is\n\n");
for(i=1;i<12;i++) printf("%c",dw[i]);
printf("\n\n enter the received hamming code\n\n");
scanf("%s",cw);
for(i=12;i>0;i--)
cw[i]=cw[i-1]; for(i=0;i<4;i++)
{
count=0;
for(j=(int)pow(2,i);j<12;j+=1;j+=(int)pow(2,i))
{
for(k=0;k<(int)pow(2,i);k++)
{
if(cw[j]=='1')count++;j++;
}
}
if (count%2!=0)
err-pos=err-post+(int)pow(2,i);
}
if(err-pos==0)
printf("\n\n there is no error in received code word \n"); else
{
if(cw[err-pos]==dw[err-pos])
{
printf("\n\n there are 2 or more errors in received code.....\n\n");
printf("sorry...! hamming code cannot correct 2 or more errors....\n");
flag=1;
}
}
else
printf("in there is an error in bit position %d of received code word \n",err-pos); if(flag==0)

```

```

{
cw[err-pos]=(cw[err-pos]=='1')?'0':'1';
printf("\n\n corrected code word is \n\n");
for(i=1;i<12;i++)
printf("%c",cw[i]);
}
}
printf("\n\n");
}

```

OUTPUT:

Enter data as binary bit stream(7 bits):

1110110

Code word is

11101100110

Enter the received hamming code 10101100110

There is an error in bit position 2 of received code word corrected code word is 11101100110

Enter data as binary bit stream(7 bits) 11101110

Code word is

11101100110

Enter the received hamming code 00101100110

There are 2 or more error in received code...

Sorry...!

Viva questions and answers:

1. Define CRC.

A cyclic redundancy check (CRC) is an error-detecting code commonly used in digital networks and storage devices to detect accidental changes to raw data.

2. Define error detection.

Error detection is the detection of errors caused by noise or other impairments during transmission from the transmitter to the receiver. Error correction is the detection of errors and reconstruction of the original, error-free data.

3. Define error correcting.

There are three main techniques for detecting errors in frames: Parity Check, Checksum and Cyclic Redundancy Check (CRC).

4. List error detecting methods.

A parity check is the process that ensures accurate data transmission between nodes during communication. A parity bit is appended to the original data bits to create an even or odd bit number; the number of bits with value one.

RESULT:

Thus the error detection/error correction techniques were implemented successfully

CONTENT BEYOND THE SYLLABUS

Write a code simulating Stop and Wait protocol.

AIM: To implement a code simulating Stop and Wait protocol.

PRE LAB DISCUSSION:

Stop-and-wait ARQ, also referred to as alternating bit protocol, is a method in telecommunications to send information between two connected devices. It ensures that information is not lost due to dropped packets and that packets are received in the correct order. It is the simplest automatic repeat-request mechanism.

ALGORITHM

Sender:

1. Start the program
2. Create socket and establish the connection with the receiver
3. Get the number of frames to be transmitted from the user
4. Get the frame size and the frames from the user
5. Send the frame to the receiver
6. Wait for the acknowledgment for the sent frame from the receiver till the timer expires
7. If the acknowledgement (ACK) received before the time expiry, get the expected frame number from the received ACK
8. If the ACK received after the timer expiry, then it is discarded
9. If the ACK is not received before the timer expiry, resend the frames for which the ACK is not received
10. Repeat the steps 4 to 9 for the number of frames to be transmitted
11. Terminate the connection
12. Stop the program

Receiver:

1. Start the program
2. Create socket and connect with the sender
3. Wait for the frames from the sender
4. Receive the frame from the sender
5. If the frame is expected frame, send the acknowledgement for the received frame to the sender
6. If the frame is not the expected frame, send the ack to the sender
7. Terminate the connection
8. Stop the program

PROGRAM

Sender:

```
import java.net.*;
import java.io.*;
import java.rmi.*;
public class server
{
public static void main(String a[])throws Exception
{
ServerSocket ser=new ServerSocket(10);
Socket s=ser.accept();
```

```

DataInputStream in=new DataInputStream(System.in);
DataInputStream in1=new DataInputStream(s.getInputStream());
String sbuff[]=new String[8];
PrintStream p;
int sptr=0,sws=8,nf,ano,i;
String ch;
do{
p=new PrintStream(s.getOutputStream());
System.out.print("Enter the no. of frames : ");
nf=Integer.parseInt(in.readLine()); p.println(nf);
if(nf<=sws-1)
{
System.out.println("Enter "+nf+" Messages to be send\n");
for(i=1;i<=nf;i++)
{
sbuff[sptr]=in.readLine();
p.println(sbuff[sptr]);
sptr=++sptr%8;
}
sws-=nf;System.out.print("Acknowledgment received");
ano=Integer.parseInt(in1.readLine());
System.out.println(" for "+ano+" frames");
sws+=nf;
}
else
{
System.out.println("The no. of frames exceeds window size");
break;
}
System.out.print("\nDo you wants to send some more frames : ");
ch=in.readLine();
p.println(ch);
}
while(ch.equals("yes"));
s.close();
}
}

```

Receiver Program

```

import java.net.*;
import java.io.*;
class client
{
public static void main(String a[])throws Exception
{
Socket s=new Socket(InetAddress.getLocalHost(),10);
DataInputStream in=new DataInputStream(s.getInputStream());
PrintStream p=new PrintStream(s.getOutputStream());
int i=0,rptr=-1,nf,rws=8;String rbuf[]=new String[8];

```

```

String ch;
System.out.println();
do{nf=Integer.parseInt(in.readLine());
if(nf<=rws-1){for(i=1;i<=nf;i++){rpctr=++rpctr%8;rbuf[rpctr]=in.readLine();
System.out.println("The received Frame " +rpctr+" is : "+rbuf[rpctr]);
}
rws-=nf;
System.out.println("\nAcknowledgment sent\n");
p.println(rpctr+1);
rws+=nf;
}
else
break;
ch=in.readLine();}
while(ch.equals("yes"));
}
}

```

```

F:\Networklab>javac MyClient.java
F:\Networklab>java MyClient
F:\Networklab>javac client.java
Note: client.java uses or overrides a deprecated API.
Note: Recompile with -Xlint:deprecation for details.
F:\Networklab>java client

The received Frame 0 is : hai
The received Frame 1 is : how are you
The received Frame 2 is : stay home
The received Frame 3 is : stay safe

Acknowledgment sent

```

Receiver window

```

F:\Networklab>javac server.java
Note: server.java uses or overrides a deprecated API.
Note: Recompile with -Xlint:deprecation for details.

F:\Networklab>java server
Enter the no. of frames : 4
Enter 4 Messages to be send

hai
how are you
stay home
stay safe
Acknowledgment received for 4 frames

Do you wants to send some more frames : _

```

VIVA(Pre & Post lab) QUESTIONS:

- 1.What is sliding window protocol?
- 2.What is stop and wait protocol?

RESULT :

Thus the program for implementing a code simulating Stop and Wait protocol was executed successfully and output is verified.

DATA COMPUTER NETWORKS LAB VIVA QUESTIONS

1. What are functions of different layers?
2. Differentiate between TCP/IP Layers and OSI Layers
3. Differentiate between TCP and UDP.
4. Differentiate between Connectionless and connection oriented connection.
5. What is meant by subnet?
6. What is meant by Gateway?
7. What is an IP address?
8. What is MAC address?
9. Define Raw Socket
10. What is a fork command?
11. Why IP address is required when we have MAC address?
12. What is meant by port?
13. What are ephemeral port number and well known port numbers?
14. What is a socket?
15. What are the parameters of socket()?
16. Describe bind(), listen(), accept(),connect(), send() and recv().
17. What are system calls? Mention few of them.
18. What is IPC? Name three techniques.
19. What type of protocol is BGP?
20. What type of protocol is OSPF?
21. Difference between ARP and RARP.
22. What is Distance Vector Routing
23. What is flooding.
24. What is three way handshake.
25. Disadvantages of Stop and wait protocol.
26. Differentiate bridges from switches.
27. What is a Router.
28. What is routing.
29. What is the role of DNS.
30. What type of transport protocol is used for DNS.